

You are required to design and implement Modern Hotel network. The hotel has three floors; in the first floor there three departments (Reception, store and Logistics), in the second floor there are three departments Finance, HR and Sales Marketing), while the third floor hosts the IT and Admin. Therefore, the following are part of the considerations during the design and implementation

1. There should be three routers connecting each floor (all placed in the server room in IT department)
2. All routers should be connected to each other using serial DCE cable.
3. The network between the routers should be 10.10.10.0/30,10.10.10.4/30,10.10.10.8/30
4. Each floor is expected to have one switch (placed in the respective floor),
5. Each floor is expected to have WIFI networks connected to laptops and phones.
6. Each department is expected to have a printer.
7. Each department is expected to be in different VLAN with the following details

1s Floor;

- Reception- VLAN 80, Network of 192.168.8.0/24.
- Store- VLAN 70, Network of 192.168.7.0 24
- Logistics- VLAN 60, Network of 192.168.6.0/24

2nd Floor;

- Finance- VLAN 50, Network of 192.168 .5.0/24
- HR- VLAN 30. Network of 192.168.4.0/24
- Sales- VLAN 310. Network of 192.168.3.0/24

3rd t Floor;

- Admin- VLAN 20, Network of 192.168.2.0/24
- IT-VLAN 10, Network of 192.168.1.0/24

8. Use OSBF as the routing protocol to advertise routes

9 All devices in the network are expected to obtain IP address dynamically with their respective router configured as the DHCP server.

10. All the devices in the network are expected to communicate with each other.

11. Configure SSH in all the routers for remote login

12. In IT department, add PC called Test-PC to port fa0/2 and use it to test remote login.